

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-22188-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 9-18S-21W  
1650 feet from N Section Line, 990 feet from W Section Line  
Lease/Unit Name: MANTZ Well Number: 2  
County: NESS Total Vertical Depth: 4300 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

Production Casing Size: 4.5 feet: 4296 WITH 100 SX CMT  
Surface Casing Size: 8.625 feet: 288 WITH 225 SX CMT

# 13975

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/22/2003 11:50 AM

Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: PUMP 200# HULLS & 20 SX CMT. PERFORATE & PUMP CMT & HULLS. PRESSURE TEST. CHECK BACKSIDE.

Plugging Proposal Received By: SCOTT ALBERG

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/22/2003 3:05 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 4265'. PERFS AT 4224-4228'. PUMPED 200#HULLS & 20 SX CMT. DISPLACED WITH 61 BBLs. MAXIMUM PRESSURE 1000 PSIG. SHUT IN PRESSURE 600 PSIG. PERFORATED 4 1/2" AT 700'. PUMPED DOWN 4 1/2" WITH 80 SX CMT - 200# HULLS - 40 SX CMT. MAXIMUM PRESSURE 300 PSIG. SHUT IN PRESSURE 0 PSIG. SHUT DOWN 15 MINUTES. TOPPED OFF 4 1/2" WITH 4 SX CMT. PUMPED 15 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS. MAXIMUM PRESSURE 500 PSIG. SHUT IN PRESSURE 500 PSIG.


RECEIVED

OCT 28 2003  
10-28-03  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE 10-28-03

AMOUNT 2004060687

FORM CR-23