

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22012-00-00
Spot: SWSEW Sec/Twnshp/Rge: 9-18S-21W
2310 feet from N Section Line, 1650 feet from W Section Line
Lease/Unit Name: MANTZ Well Number: 1
County: NESS Total Vertical Depth: 4281 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

Production Casing Size: 4.5 feet: 4275 WITH 100 SX CMT
Surface Casing Size: 8.625 feet: 330 WITH 250 SX CMT

#139'3

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/22/2003 12:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: PUMP 200# HULLS & 20 SX CMT. PERFORATE AND FILL 4 1/2" TO SURFACE WITH CMT. CHECK BACKSIDE.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/22/2003 2:25 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:
PBTD 4251'. PERFS AT 4200-4206'. PUMPED 200# HULLS & 20 SX CMT. DISPLACED WITH 61 BBLs. MAXIMUM PRESSURE 800 PSIG. SHUT IN PRESSURE 400 PSIG. PERFORATED 4 1/2" @ 700'. PUMPED 180 SX CMT DOWN 4 1/2". CIRCULATED CMT TO SURFACE UP 8 5/8" X 4 1/2" ANNULUS FROM 700'.

RECEIVED
OCT 28 2003
10-28-03
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
OCT 24 2003
KCC Dodge City

Signed Richard W. Lacey

(TECHNICIAN)
INVOICED
DATE 10-28-03
CV. NO. 2004060687

Form 67-26