

1 060532

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,797-0000

NE SE SE, SEC. 8, T 18 S, R 21 W/EX

990 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5040

Lease Name Fritz Well # 1

Operator: Alpine Drilling Co., Inc.

County Ness 140.24

Name & Address 200 E. First, Suite 500

Well Total Depth 4315 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 329

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Alpine Drilling Co., Inc. License Number 5040

Address 200 East First, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 1:00 pm Day: 3 Month: April Year: 19 85

Plugging proposal received from Walt Coldwater

(company name) Alpine (phone) 316-263-5705

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1470' with 50 sx cement

2nd plug at 730' with 50 sx cement

3rd plug at 350' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement
Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:30 pm Day: 3 Month: April Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1470' with 50 sx cement, 2nd plug at 730' with 50

sx cement, 3rd plug at 350' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1985
4-12-85

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(Check / did not) observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE 4-16-85

INV. NO. 7737