

1 050798

209 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,021-0000
Approx. NE, NW, SEC. 6, T 18 S, R 21 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 9746
Operator: Wilkar Oil Company
Name & Address: 10707 Norwalk Blvd.
Santa Fe Springs, CA 90670

2300 feet from S section line
4200 feet from E section line
Lease Name Pember Well # 1
County Ness 146.12
Well Total Depth 4496 Mississippi feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 5:00 am Day: 20 Month: April Year: 19 86

Plugging proposal received from Kenneth Lyle

(company name) Red Tiger (phone) 316-263-1201
Elevation 2264'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1580-90'

1st plug at 1588' with 50 sx cement

2nd plug at 750' with 75 sx cement

3rd plug at 290' with 40 sx cement

4th plug from 40' to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:00 am Day: 20 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1588' with 50 sx cement, 2nd plug at 750' with 75 sx

cement, 3rd plug at 290' with 40 sx cement, 4th plug from 40' to surface with 10 sx

cement, 5th plug to circulate rat hole with 15 sx cement.

Mud Info: 42 Viscosity 9.9 ppg (Tagged 1st plug at 1600' after 4 hours.)

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

APR 29 1986

DATE

INV. NO. 13608

4-20

Signed Richard M. Lacey (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION
APR 28 1986
4-28-86
CONSERVATION DIVISION
Wichita, Kansas