

2-2/ R

To: 1 110130
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,328-~~6660~~
50' E of
C. NE SW, SEC. 5, T. 18 S, R. 21 W
1980 feet from S section line
3250 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3532

Lease Name Ross Well # 1-5

Operator: CMX, Inc.
Name & Address 1026 Union Center Building
Wichita, KS 67202

County Ness 139.26
Well Total Depth 4285 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 299

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 310 West Central, Suite 117, Wichita, KS 67202

Company to plug at: Hour: 8:13 a.m. Day: 21 Month: 2 Year: 1989

Plugging proposal received from Ervin Neighbors

(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1469-1500'
1st plug at 1500' with 50 sx cement, 2nd plug at 800' with 80 sx cement,
3rd plug at 330' with 50 sx cement,
4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10 a.m. Day: 21 Month: 2 Year: 1989

ACTUAL PLUGGING REPORT 1st plug at 1500' with 50 sx cement,
2nd plug at 800' with 80 sx cement,
3rd plug at 330' with 50 sx cement,
4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
3-10-89
MAR 10 1989

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-14-89
INV. NO. 24082

Signed James R. Kay (TECHNICIAN)

135-23,328-0000

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date ... January 26, 1989 ...
month day year

50' East of
C... NE... SW. Sec 5... Twp 18. S, Rg 21... West

OPERATOR: License # 03532
Name: CMX, Inc.
Address: 1026 Union Center Building
City/State/Zip: Wichita, Kansas 67202
Contact Person: Doug McGinness II
Phone: (316) 269-9052

1980
3250
feet from South line of Section
feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 5929
Name: Duke Drilling Co., Inc.

County: Ness
Lease Name: Ross Well #: 1-5
Field Name: Wildcat
Is this a Prorated Field? ... yes no
Target Formation(s): Ft. Scott/Cherokee/Miss
Nearest lease or unit boundary: 610'
Ground Surface Elevation: 2195 feet MSL
Domestic well within 330 feet: ... yes no
Municipal well within one mile: ... yes no
Depth to bottom of fresh water: 100'
Depth to bottom of usable water: 850'
Surface Pipe by Alternate: 1 2
Length of Surface Pipe Planned to be set: 280'
Length of Conductor pipe required: N/A
Projected Total Depth: 4300'
Formation at Total Depth: Mississippi
Water Source for Drilling Operations:
... well farm pond ... other

Well Drilled For: Well Class: Type Equipment:
 Oil ... Inj ... Infield Mud Rotary
 Gas ... Storage ... Pool Ext. ... Air Rotary
 OAWD ... Disposal Wildcat ... Cable
 Seismic; ... # of Holes

If OAWD: old well information as follows:
Operator: ...
Well Name: ...
Comp. Date: ... Old Total Depth: ...

Directional, Deviated or Horizontal wellbore? ... yes no
If yes, total depth location: ...

DWR Permit #: N/A
Will Cores Be Taken? ... yes no
If yes, proposed zone: ...

280' Spud - 2-13-89 Haul well 200' alt. 2 Reg.

PUSHER Swain Reighouse
 TD 4285' FORMATION Miss
 SURFACE PIPE 8 3/8 @ 2 9/9
 ANHYDRITE 1469 ELEVATION 2500
 STARTING TIME & DATE 8:13 AM
 COMPLETION TIME & DATE 10:00 AM
 1st PLUG @ 1500 FT. WI 5" O SX
 2nd PLUG @ 800 FT. WI 8" O SX
 3rd PLUG @ 330 FT. WI 5" O SX
 4th PLUG @ 40-0 FT. WI 1" O SX
 RAT HOLE CIRCULATED W/ 1 1/2" SX
 MOUSE HOLE CIRCULATED W/ SX
 WATER WELL PLUGGED W/ SX
 CEMENT COMPANY P. G. Zink
 TECHNICIAN P. G. Zink

RECEIVED
STATE CORPORATION COMMISSION
MAR 10 1989
CONSERVATION DIVISION
Wichita, Kansas

5280	
4950	
4620	
4290	
3960	
3630	
3300	
2970	
2640	
2310	
1980	
1650	
1320	
990	
660	
330	

CONSERVATION DIVISION
Wichita, Kansas

Spud date: _____ Agent: _____

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
 - File Completion Form ACO-1 within 120 days of spud date;
 - File acreage attribution plat according to field proration orders;
 - Notify appropriate district office 48 hours prior to workover or re-entry;
 - Submit plugging report (CP-4) after plugging is completed;
 - Obtain written approval before disposing or injecting salt water.