

070668

5-3

23333

To: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,333-0000
C. NE SE, SEC. 3, T 18 S, R 21 W/EX
1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3667

Lease Name Pabst "A" Well # 2

Operator: Source Petroleum
Name & Address 200 West Douglas, Suite 320
Wichita, KS 67202

County Ness 139.26

Well Total Depth 4285 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 210

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Plains Inc. License Number 4072

Address P.O. Box 346, Ness City, KS 67560

Company to plug at: Hour: 12:15 p.m. Day: 3 Month: 5 Year: 19 89

Plugging proposal received from Clint Base

(company name) Plains Inc. (phone) 913-798-3995

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2138'
Anhydrite 1389-1442'

- 1st plug at 1430' with 50 sx cement, 2nd plug at 800' with 80 sx cement,
- 3rd plug at 240' with 40 sx cement,
- 4th plug at 40' with 10 sx cement,
- 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 3 Month: 5 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 1440' with 50 sx cement,

2nd plug at 880' with 80 sx cement,

3rd plug at 230' with 40 sx cement,

4th plug at 50' with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
STATE DEPARTMENT

MAY 9 1989
5-9-89
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
I intend to observe this plugging.

DATE 5-10-89

Signed Dan Johnson
(TECHNICIAN)

INV. NO. 24744

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date: March 6, 1989
 month day year

Gen NE SE Sec 3 Twp 18S Rg 21 East
 West

OPERATOR: License # 3667
 Name: Source Petroleum a Div. of Presley Petroleum Co.
 Address: 200 W. Douglas, Ste 820
 City/State/Zip: Wichita, KS 67202
 Contact Person: John D. Howard, Jr.
 Phone: 316-262-7397

1980' feet from South line of Section
 660' feet from East line of Section
 (Note: Locate well on Section Plat Below)

CONTRACTOR: License #: Unknown Allen
 Name: _____

County: Ness
 Lease Name: Pabst "A" Well #: 2
 Field Name: N/A

Well Drilled For: Well Class: Type Equipment:
 Oil ... Inj ... Infield Mud Rotary
 Gas ... Storage ... Pool Ext. ... Air Rotary
 OAWO ... Disposal Wildcat ... Cable
 Seismic; ... # of Holes

Is this a Prorated Field? ... yes no
 Target Formation(s): LKC, Ft. Scott, Cherokee, Mississipp
 Nearest lease or unit boundary: 660'
 Ground Surface Elevation: 2138' feet MSL
 Domestic well within 330 feet: ... yes no
 Municipal well within one mile: ... yes no
 Depth to bottom of fresh water: ... 180'
 Depth to bottom of usable water: ... 500' 750'
 Surface Pipe by Alternate: ... 1 2
 Length of Surface Pipe Planned to be set: ... 200'
 Length of Conductor pipe required: ... NONE
 Projected Total Depth: ... 4300'
 Formation at Total Depth: ... Mississippi
 Water Source for Drilling Operations:
 ... well ... farm pond other

If OAWO: old well information as follows:
 Operator: _____
 Well Name: _____
 Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? ... yes no
 If yes, total depth location: _____

DWR Permit #: _____
 Will Cores Be Taken?: ... yes no
 If yes, proposed zone: _____

Get 200' of 8 3/8" on 3/8-89. 200' Act 2 Reg

*Moved off on 3-16-89.
 Did not plug - TAD*

PUSHER Vince Schappert
 TD 4285 FORMATION MISS
 SURFACE PIPE 8 3/8" @ 210
 ANHYDRITE 1290-1422 ELEVATION 2138 S.L.
 STARTING TIME & DATE _____
 COMPLETION TIME & DATE _____
 1st PLUG @ 1430 FT. W/ 50 SX
 2nd PLUG @ 800 FT. W/ 80 SX
 3rd PLUG @ 240 FT. W/ 40 SX
 4th PLUG @ 40 FT. W/ 10 SX
 RAT HOLE CIRCULATED W/ 15 SX
 MOUSE HOLE CIRCULATED W/ _____ SX
 WATER WELL PLUGGED W/ _____ SX

AFFIDAVIT

CEMENT COMPANY _____
 MAY 1989
 CONSERVATION COMMISSION
 9/40 @ page

5280	1650
4950	1320
4620	990
4290	660
3960	330
3630	
3300	
2970	
2640	
2310	
1980	
1650	
1320	
990	
660	
330	

CONSERVATION
 Wichita, Kansas

Spud date: _____
 Agent: _____

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
 - File Completion Form ACO-1 within 120 days of spud date;
 - File acreage attribution plat according to field proration orders;
 - Notify appropriate district office 48 hours prior to workover or re-entry;
 - Submit plugging report (CP-4) after plugging is completed;
 - Obtain written approval before disposing or injecting salt water.