

To: 1 060015 2-6
STATE CORPORATION COMMISSION
Wichita, State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 135-22,060-0660
App. C NE NW, SEC. 3, T 18 S, R 21 W/8
4620 feet from S section line
3150 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9860
Operator: Castle Resources Inc.
Name & Address: 1200 E. 27th
Hays, KS 67601

Lease Name McCormick Well # 2
County Ness 136.82
Well Total Depth 4210 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 408

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____
Address _____

Company to plug at: Hour: 2 p.m. Day: 6 Month: 2 Year: 19 97
Plugging proposal received from Dean Ives

(company name) Castle Resources Inc. (phone) 913-483-2662

Work: 4 1/2" at 4189' w/125 sx cement, PBD 4160', Perfs at 4088-92'
1st plug pump 200 lbs. hulls and 20 sx cement,
2nd plug perforate at 750' and circulate cement to surface.
Check backside.

46-111-0

Plugging Proposal Received by Kevin Strube (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 6 Month: 2 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 20 sx cement, displaced to bottom until pressured to 800#,

2nd plug shot perfs at 750', pumped 200 sx cement down casing and circulated 5 sx cement out backside.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE FEB 13 1997
INV. NO. 47571
2-6

Signed Michael J. Mace (TECHNICIAN)