

To: 1 070138
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5430

Operator: Energy Three, Inc.
Name & Address: P. O. Box 1505
Great Bend, KS 67530

API NUMBER 15- 135-22,984-0000

C NE NE, SEC. 1, T 18 S, R 21 W/E
4620 feet from S section line
660 feet from E section line

Lease Name Ryan Well # 1

County Ness 138.45

Well Total Depth 4260 Cherokee Sand feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 290

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Big Three Drilling Co., Inc. License Number 5836

Address P. O. Box 52, Gorham, KS 67640

Company to plug at: Hour: 5:30 pm Day: 12 Month: February Year: 19 86

Plugging proposal received from Stan Lovelady

(company name) Big Three (phone) 913-637-5487

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2170'
Anhydrite 1405'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 75 sx cement

3rd plug 30' below the base of the surface pipe with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15sx cement, 7th plug to circulate mouse hole with
10 sx cement Plugging Proposal Received by Dan Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 8:00 pm Day: 12 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1426' with 50 sx cement, 2nd plug at 810' with 75 sx
cement, 3rd plug at 320' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with
15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED

STATE CORPORATION COMMISSION

FEB 17 1986

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan

(If additional description is necessary, use BACK of this report)

INVOICED
I did observe this plugging.

DATE 1-17-86

INV. NO. 12625

2-12

Signed Dan Goodrow
(TECHNICIAN)

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
 (see rules on reverse side)

CARD MUST BE SIGNED

Starting Date DECEMBER 23 1985
 month day year

API Number 15— 135-22,984-0000

OPERATOR: License # 5430
 Name ENERGY THREE, INC.
 Address P. O. Box 1505
 City/State/Zip GREAT BEND, KANSAS 67530
 Contact Person CHARLES DIXON
 Phone AC316-792-5968

CENT. NE NE Sec. 1 Twp. 18 S, Rg. 21 — East
1620 Ft. from South Line of Section
660 Ft. from East Line of Section
 (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5836
 Name BIG THREE DRILLING, INC.
 City/State Box 52, GORHAM, KS. 67640

Nearest lease or unit boundary line 660 feet
 County NESS

Lease Name RYAN Well # 1

Ground surface elevation 660 feet MSL

Domestic well within 330 feet: —yes X no

Municipal well within one mile: —yes X no

Surface pipe by Alternate: 1 — 2 X0

Depth to bottom of fresh water 75

Depth to bottom of usable water 500

Surface pipe planned to be set 200' (8 5/8")

Projected Total Depth 4250 feet

Formation CHEROKEE SAND

Well Drilled For: Well Class: Type Equipment:
☒ Oil ☐ SWD ☐ Infield ☒ Mud Rotary
☐ Gas ☐ Inj ☐ Pool Ext. ☐ Air Rotary
☐ OWWO ☐ Expl ☒ Wildcat ☐ Cable

If OWWO: old well info as follows:

Operator _____
 Well Name _____
 Comp Date _____ Old Total Depth _____

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

12-12-85 cementing will be done immediately upon starting production casing.

Date 12-12-85 Signature of Operator or Agent Charles Dixon Title EXECUTIVE VICE-PRES.

For KCC Use:

Conductor Pipe Required _____ feet; Minimum Surface Pipe Required _____ feet per Alt. 1 2 0

This Authorization Expires 6-13-88 Approved By 12-13-85 NO

2-b-86 - move in
 8 5/8 - 240' - 250'

PUSHER	TD	INFORMATION	SURFACE PIPE	ANHYDRITE	ELEVATION	STARTING TIME & DATE	COMPLETION TIME & DATE	1st PLUG @	2nd PLUG @	3rd PLUG @	4th PLUG @	RAT HOLE CIRCULATED W/	MOUSE HOLE CIRCULATED W/	WATER WELL PLUGGED W/	CEMENT COMPANY	TECHNICIAN
								FT. W/	FT. W/	FT. W/	FT. W/					

RECEIVED
 STATE CORPORATION COMMISSION

FEB 17 1986

CONSERVATION DIVISION
 Wichita, Kansas

50 SX. - base Any.
 75 SX. - base cheyenne
 30' below SP. - 50 SX.
 40' - SP. + 10 SX.
 15 - rat
 10 - mouse