

1 080245

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-20,737 -0000

NE NW SW , SEC. 28 , T 32 S, R 14 W/E
N SE Corner of
2110 feet from ~~XXX~~ section line
W SE Corner of
4455 feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Allen Well # C-1

Operator: TXO Production Corp.

County Barber

Name & Address 200 W. Douglas, Suite 300

Well Total Depth 4887 158.73 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 335

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:00 am Day: 22 Month: October Year: 19 84

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 2 7/8" at 4880'

1st plug pump 20 sx cement to bottom and stop plug at 4000'

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 100 sx cement.

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:00 noon Day: 22 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 2 7/8" set at 4880'

1st plug pumped 20 sx cement to bottom and stopped plug at 4000', 2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 100 sx cement.

STATE CORPORATION COMMISSION

Maximum pressure 300 psi and shut in pressure 100 psi

OCT 31 1984

10-31-84
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Recovered 3405' 2 7/8" casing. Used Class A cement by Sun.

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed J. H. Metz (TECHNICIAN)

INVOICED

DATE 11-7-84

INV. NO. 4693