

1 010010

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C N/2  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,686-0000  
NW NE, SEC. 28, T 32 S, R 14 W/EXX

4950 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5171

Lease Name Marsh "A" Well # 1  
County Barber 159.25

Operator: TXO Production Corp.  
Name & Address 200 W. Douglas, Suite 300  
Wichita, KS 67202

Well Total Depth 4900 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 430 ✓

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:00 pm Day: 29 Month: July Year: 19 85

Plugging proposal received from Elmo Morgenstern  
(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 4890' PBD 4810' Perfs at 4756-60'  
1st plug sand back to 4700' and dump 4 sx cement on top of sand through bailer  
2nd plug squeeze well with 3 sx hulls, 20 sx gel, 1 sack hulls, release 8 5/8" rubber plug  
and pump 125 sx cement.

Plugging Proposal Received by Robert B. Tarbutton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:30 pm Day: 29 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 4 sx cement on top of  
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 20 sx gel, 1 sack hulls,  
released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 250 psi and shut in 50 psi

Remarks: Recovered 4200' 4 1/2" casing. Cemented by BJ-Titan  
(If additional description is necessary, use BACK of this form.)

INVOICED  
AUG 07 1985

RECEIVED  
STATE CORPORATION COMMISSION  
Signed

*Robert B. Tarbutton*  
(TECHNICIAN)

DATE 9438  
INV. NO. 9438

AUG 2 1985  
8-2-85  
CONSERVATION DIVISION