

1080555

87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,723-0000

NW NE NW, SEC. 28, T 32 S, R 14 (W/E)

4950 feet from S section line

3430 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Fritz "A" Well # 1

Operator: TXO Production Corporation

County Barber 159.25

Name & Address

Well Total Depth 4900 feet

155 N. Market, Suite 1000

Conductor Pipe: Size _____ feet

Wichita, KS 67202

Surface Casing: Size 8 5/8 feet 432

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor TXO Production Corporation License Number 5171

Address 155 N. Market, Suite 1000, Wichita, KS 67202

Company to plug at: Hour: 2 p.m. Day: 14 Month: 10 Year: 19 86

Plugging proposal received from Leamon Roberson

(company name) TXO (phone) 316-886-5606

were: 4 1/2" at 4899' PBD 4880' Perfs 4696-4701'

1st plug sand back to 4650' and dump 4 sx cement on top of sand through bailer.

2nd plug squeeze well with 3 sx hulls, 20 sx gel, and pump 100 sx lite cement.

Plugging Proposal Received by Don Ubel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:50 p.m. Day: 14 Month: 10 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4650' and dumped 4 sx cement on top of sand through bailer.

2nd plug squeezed well with 3 sx hulls, 20 sx gel, and 100 sx thrifty light cement.

Note: Clarke Oilfield Services of Medicine Lodge, KS pulled casing but were not on location when well was plugged.

Maximum pressure 300 psi and shut in 150 psi.

Remarks: Used thrifty light cement by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-20-86

INV. NO. 15208

Signed J. N. [Signature] (TECHNICIAN)

FILED STATE CORP. CONSERVATION DIV. WICHITA, KS OCT. 20 1986