

1120019

*R*

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C N/2 N/2, SEC. 22, T 32 S, R 14 W/8  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- - 007-22,046-0000

NE

SEC. 22, T 32 S, R 14 W/8

4950 FEET FROM N/S SECTION LINE

1320 FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5087

LEASE NAME Hinz WELL # "A" 2-22

OPERATOR: Texas Energies, Inc.  
NAME & ADDRESS: P. O. Box 947  
Pratt, KS 67124

COUNTY Barber 163.94  
(Miss. Kinderhook)

WELL TOTAL DEPTH 4684 FEET

CONDUCTOR PIPE: SIZE \_\_\_\_\_ FEET \_\_\_\_\_

SURFACE CASING: SIZE 8 5/8 FEET 1006

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D&A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR Wheatstate Oilfield Services, Inc. LICENSE NUMBER 5149

ADDRESS P. O. Box 329, Pratt, KS 67124

COMPANY TO PLUG AT: HOUR: 2:00 am DAY: 17 MONTH: June YEAR: 19 85

PLUGGING PROPOSAL RECEIVED FROM Dennis Petz

(COMPANY NAME) Wheatstate (PHONE) 316-672-7514  
Elevation 1826

WERE: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1000

1st plug at 1060' with 50 sx cement

2nd plug at 500' with 30 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

PLUGGING PROPOSAL RECEIVED BY Don C. Ubel

(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL \_\_\_\_\_ PART \_\_\_\_\_ NONE

OPERATIONS COMPLETED: HOUR: 4:00 am DAY: 17 MONTH: June YEAR: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1060' with 50 sx cement, 2nd plug at 500' with 30  
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface  
with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 21 1985

6-21-85  
CONSERVATION DIVISION  
WICHITA, KANSAS

REMARKS: Used 60/40 Pozmix 6% gel by BJ-Titan.

I ~~(DID)~~ / DID NOT) OBSERVE THIS PLUGGING.

SIGNED

*Don C. Ubel*  
(TECHNICIAN)

INVOICED

DATE 6-25-85

INV. NO. 8692

6-17

FORM CP-2/3  
REV. 6-83