

15-135-21122-0500


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ness County, Sec. 7 Twp. 18S Rge. (E) 21 (W)  
Location as "NE/CNWxSWx" or footage from lines C SE NW  
Lease Owner O. A. Sutton  
Lease Name Roth Well No. 1  
Office Address 800 Sutton Place, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 30 1975  
Application for plugging filed November 30 1975  
Application for plugging approved November 30 1975  
Plugging commenced November 30 1975  
Plugging completed November 30 1975  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4350 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	457'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug at 600' with 50 sacks; plug at 300' with 25 sacks; solid  
bridge and plug at 40' with 10 sacks. Job complete at 12:15 p.m.  
11-30-75. Job by Howco.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 10 1975  
12-10-75  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.  
Address 830 Sutton Place, Wichita, Kansas 67202


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Jack G. Paulsen (employee of owner) ~~not owner or operator~~ of the above-described

well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack G. Paulsen  
Jack G. Paulsen  
800 Sutton Place, Wichita, Kansas 67202  
(Address)

Subscribed and sworn to before me this 9th day of December, 1975.

My commission expires June 28, 1978.  
Jean S. Taylor Notary Public.



GABBERT-JONES, INC.  
 WICHITA, KANSAS  
 DRILLERS' WELL LOG

Roth #1  
 C-SE-NW Sec 7-18S-21W  
 Ness County Kansas

Commenced: 11-18-75

Completed: 11-30-75

OPERATOR: O. A. SUTTON

15135-2122-0000

Depth From	To	Formation	Remarks
0	68	Surface Clay-Sand	Ran 11 jts. of used 8 5/8" csg
68	246	Post Rock-Shale-Sand	set @ 457' Cemented w/
246	461	Shale w/sand stks	300 sks common 2% Gel
461	859	Shale-Redbed-Sand Stks	3% CC PD @ 6:15 a.m.
859	980	Shale-Redbed	11-19-75
980	1180	Sand	
1180	1511	Shale-Redbed	
1511	1545	Anhy	
1545	2160	Shale-Shells	
2160	3836	Lime-Shale	
3836	4350	Lime	
	4350 - TD		DRY & ABANDONED

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled C-SE-NW Sec 7-18S-21W, Ness County Kansas to the best of my knowledge and belief.

*James S. Sutton II*  
 JAMES S. SUTTON II

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said county and State, on this 8th day of December, 1975, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

*Elizabeth J. Edwards*  
 ELIZABETH J. EDWARDS-NOTARY PUBL

My Commission Expires: February 6, 1979.

RECEIVED  
 STATE CORPORATION COMMISSION

DEC 10 1975

CONSERVATION DIVISION  
 Wichita, Kansas

