

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-23,328-0000

LEASE NAME Ross

WELL NUMBER 1-5

1980 Ft. from S Section Line

3250 Ft. from E Section Line

SEC. 5 TWP. 18 RGE. 21 (E) or (W)

COUNTY Ness

Date Well Completed 2-21-89

Plugging Commenced 2-21-89

Plugging Completed 2-21-89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR CMX, Inc.

ADDRESS 1026 Union Center Bldg. Wichita, KS 67202

PHONE# (316) 792-7476 OPERATORS LICENSE NO. 3532

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-17-89 (date)

by Mr. Luthi (KCC District Agent's Name).

Is ACO-1 filed? operator to be filed by operator If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4285

Show depth and thickness of \_\_\_\_\_, oil and gas formations.

OIL, GAS OR WATER RECORD \_\_\_\_\_ CASING RECORD \_\_\_\_\_

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Bottom Plug: @1500' w/50 sacks cement thru drill pipe  
Next Plug: @ 800' w/80 " " " " "  
Next Plug: @ 330' w/50 " " " " "  
Top Plug: @ 40' w/10 " " " " " 15 sacks in Rat Hole  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo drilling Company License No. 5864

Address P.O. Box 877 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: CMX Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Ervin Neighbors (Employee of Operator) or ~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.

(Signature) Ervin Neighbors

(Address) P.O. Box 877 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 27 day of February, 1989

Dorothy M. Hogue  
Notary Public

My Commission Expires: 5-5-90

75 135 23328 0000

DRILLER'S WELL LOG

DATE COMMENCED: February 13, 1989  
DATE COMPLETED: February 21, 1989

GMX, Inc.  
Ross #1-5  
50' E. of C NE SW  
Sec. 5, T18S, R21W  
Ness County, Ks.

ELEVATION: 2195 K.B.

0	-	391'	Surface Soil, Clay, Shale
391	-	890'	Sand & Shale
890	-	1140'	Sand
1140	-	1469'	Shale
1469	-	1500'	Anhydrite
1500	-	1900'	Shale
1900	-	2590'	Lime & Shale
2590	-	2958'	Shale & Lime
2958	-	3125'	Lime
3125	-	3564'	Shale & Lime
3564	-	3758'	Lime
3758	-	4010'	Lime & Shale
4010	-	4205'	Lime
4205	-	4261'	Lime & Shale
4261	-	4260'	Chert & Lime
4260	-	4285'	Lime
		4285'	RTD

Surface Pipe: Set new  
R 5/8" 20# pipe 0299  
w/165 sacks 60/40 pozmix  
2% gel 3% cc

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 28 1989  
CONSERVATION DIVISION  
Wichita, Kansas

*Ervin Neighbors*

Subscribed and sworn to before me this 27 day of February 1989.

*Dorothy M. Hague*  
Notary Public

DOROTHY M. HAGUE  
NOTARY PUBLIC  
STATE OF KANSAS  
And. Exp. 5-5-90