

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15-135-21996-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Ness SEC. 3 TWP. 18s RGE. 21w E/W
 Location as in quarters or footage from lines:
C of NW NE

Locate Well
 correctly on above
 Section Platt.

Lease Owner Hummon Corp.
 Lease Name Pabst #2 Well No. _____
 Office Address 400 One Main Place, Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 5/11/83
 Plugging completed 5/13/83
 Reason for abandonment of well or producing formation _____

_____ Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4200'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	380'	none
				4 1/2"	4199'	3005'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Plugged bottom hole back with sand to 4075' & ran 4 sacks cement. Shot
casing at 3410', 3210', & 3005'. Pulled total of 75 joints of pipe.
Squeezed hole with 3 hulls, 15 gel, 70 cement, 10 gel, & 1 hull. Released
plug & displaced with 200 sacks cement.

Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of May, 19 83

My Commission expires:



RECEIVED
 STATE CORPORATION COMMISSION
 Public.
5-19-83
MAY 19 1983

15-135-219960000

DRILLERS LOG

No. 2 Pabst

CASING RECORD:	COMPANY:	Hummon Corporation	DESCRIPTION:
8 5/8" @ 380' w/225 sx cement	CONTRACTOR:	Red Tiger Drilling Company	C NW/4 NE/4 Sec. 3-T18S-R21W Ness County, Kansas
4 1/2" @ 4,199' w/125 sx cement	COMMENCED:	April 22, 1981	
TOTAL DEPTH: 4,200'	COMPLETED:	April 30, 1981	ELEVATION: 2,136' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay & Post Rock	0	40	
Shale	40	820	
Sand	820	1050	
Shale	1050	1386	
Anhydrite	1386	1417	
Shale	1417	2060	
Shale & Lime	2060	3000	
Lime & Shale	3000	3670	
Lime	3670	4135	
Lime & Sand	4135	4147	
Lime	4147	4200	
RTD		4200	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 5th day of May, 1981.

Joyce A. Baer
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

APR 15 1983

CONSERVATION DIVISION
Wichita, Kansas

