


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Ness County, Sec. 1 Twp. 18S Rge. 21WE/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE NW SE

Lease Owner D N B DRILLING, INC.
Lease Name Lamer 'A' Well No. 1
Office Address 701 First Nat'l Bldg., Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed 9-9- 1976
Application for plugging filed 9-9 1976
Application for plugging approved 9-9 1976
Plugging commenced 9-9 1976
Plugging completed 9-9 1976

Reason for abandonment of well or producing formation
No commercial quantities of oil or gas encountered.
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4200
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Shale	Surf	352	8-5/8"	345	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Fluid to 500', plug, 50 sx cement;
Fluid to 240', plug, 25 sx cement;
Fluid to 40', plug, 1/2 sx hulls, 10 sx cement

STATE CORPORATION COMMISSION

SEP 20 1976
9-20-76
CONSERVATION DIVISION

(If additional description is necessary, use back of this sheet)
Name of Plugging Contractor D N B DRILLING, INC.
701 First National Building
Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF _____, ss.
JAMES L. DONELSON (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson
701 First Nat'l Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of Sept., 19 76

Ella Priess
Notary Public.

My commission expires ~~8-25-76~~ 8-25-80 Ella Priess



DRILLERS' LOG

15135 21250 0000

D N B DRILLING, INC.
No. 1 Lamer 'A'
SE NW SE, Sec. 1-18S-21W
Ness County, Kansas

Elev: 2136 K.B.

Commenced: 9-3-76
Completed: 9-9-76

Surface Casing: 345' of
8-5/8" cemented w/225 sx
common cement, 28 Gel, 38 cc.
9-3-76

FORMATION

DEPTH

Surface Hole	0 - 352
Shale	352 - 1372
Anhydrite	1372 - 1403
Shale	1403 - 1800
Shale & Lime	1800 - 2040
Shale	2040 - 2100
Lime & Shale	2100 - 2385
Shale & Lime	2385 - 2590
Lime & Shale	2590 - 2825
Shale & Lime	2825 - 3285
Lime & Shale	3285 - 3980
Lime	3980 - 4200 RTD

SEP 20 1976
CONSERVATION DIVISION
Topeka, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 16th day of Sept. 1976.

Ella Priess
Ella Priess, Notary Public

