


STATE OF KANSAS
STATE CORPORATION COMMISSION

**Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:**
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas



WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

**Strike out upper line
when reporting plug-
ging off formations.**

Barber County. Sec. 27 Twp. 32S Rge. 14 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. SW - SE - NW $\frac{1}{4}$

Lease Owner. OLSON OIL COMPANY

Lease Name..... J. C. ELSEA

Well No. 1

Office Address Drawer 588, Tulsa, Oklahoma

Character of Well (Completed as Oil, Gas or Dry Hole)..... **Dry**

Date, well completed 11 - 14 - 1937

Application for plugging filed _____ 11 - 29 - 1937

Application for plugging approved..... 12 - 3 - 1937

Plugging Commenced.....	12 - 4 -	1937
-------------------------	----------	------

Plugging Completed..... 12 - 13 - 1937

Reason for abandonment of well or producing formation..... **Dry**

If a producing well is abandoned, date of last production.....193.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? **Yes**

Name of Conservation Agent who supervised plugging of this well. C. T. Alexander

Producing formation..... Depth to top..... Bottom..... Total Depth of Well **5248** Feet.

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Hole plugged back with 3 sacks of cement at bottom of liner and bridged at top of liner (4960') with plug & rocks and dumped 25 sacks of cement, filled to 4884. Filled hole with mud to bottom of surface pipe. Dumped 11 sacks of cement, filled hole 15 ft. Filled to 3 ft. of top with heavy mud and capped with 3 sacks of regular cement.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....Mr. C. L. Barrett,
Address.....Box 408, Burrton, Kansas

STATE OF Kansas COUNTY OF Reno, ss.

C. L. Barrett (employee of owner) or ~~partner or operator~~ of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. L. Barrett

Box 408 Burton House
(Address)

SUBSCRIBED AND SWORN TO before me this 17 day of December, 1937.


My commission expires _____

4/20/38

17-932 9-37-5M

.....
Notary Public.

OLSON OIL COMPANY
J. C. ELSEA # 1
2310' NL, 1790' WL.
SW SE NW Sec. 27-32-37-14W
BARBER COUNTY, KANSAS




COMMENCED 8 - 10 - 37
COMPLETED 11 - 14 - 37
ELEVATION 1903'
INT. PROD. DRY

0
55 Sand & rock
135 Red rock
180 Red rock & shale
210 Red rock
385 Red rock & Gyp.
730 Shale
870 Red rock
930 Shale, Red rock & Gyp.
1070 Shale
1105 Red rock & shale
1215 Shale
1364 Shale, shells & Gyp.
1443 Shale
1512 Lime, shells, & Gyp.
70 Lime & shale
1750 Shale
1800 Shale & lime shells
10 Shale
37 Lime
1921 Broken lime
2014 Broken lime & shale
2150 Lime
80 Lime & shells
2260 Lime, shells & Gyp.
77 Red rock & Gyp.
2328 Shale & Gyp.
83 Red rock, shale & Gyp.
2415 Lime
54 Lime, shale, & Gyp.
80 Shale & Gyp.
99 Broken lime & shells
2527 Lime
2591 Broken lime
2633 Lime & shale
85 Lime
2722 Lime & shells
45 Lime
50 Slate
2806 Lime
55 Lime & shale
62 Broken lime
80 Lime
82 Shale, sticky
2929 Lime & shale
38 Shale
3050 Lime
3115 Lime
50 Shale & shells
63 Lime

3211 Lime & shale
61 Red Bed & shale
97 Lime
3337 Shale & lime shells, sticky
87 Lime & shale
3426 Broken lime
89 Lime
3519 Broken lime & shale
50 Broken lime
95 Lime, porous
3601 Lime
51 Lime, hard
61 Shale, black & sticky
84 Sandy lime & shale
3710 Shale & shells
22 Lime
3835 Shale
40 Lime, hard
72 Shale
3925 Lime & shale
55 Shale
85 Lime
4006 Shale
49 Lime
4120 Shale
43 Lime
49 Sand, hard
62 Sand, soft
78 Shale
4203 Lime
25 Lime, sandy
36 Lime
76 Lime, sandy
4314 Broken lime
22 Lime
98 Broken lime
4406 Lime
64 Lime & chert
68 Broken lime & shale
75 Lime & chert
99 Lime
4523 Broken lime
72 Lime
83 Lime & chert
4602 Broken lime
51 Lime
82 Lime & shale
96 Lime, hard
4712 Lime
36 Lime & chat

PLUGGING

FILE SEC 27-32-37-14W
BOOK PAGE 120 LINE 14



15-037-10115-0000

2 -

OLSON OIL COMPANY
J. C. ELSEA # 1COMMENCED 8 - 10 - 37
COMPLETED 11 - 14 - 37

WELL LOG (Continued)

4762 Lime
94 Broken lime & shale
4858 Lime & shale
4933 Lime
55 Lime & shale
68 Lime - Core
73 Lime - Core
83 Lime - Core
88 Lime - Core
4991 S.L.C. - R.U.S.T.
5000 Viola Lime
25 Viola Lime
34 " " , hard & sharp
51 " " "
47 " " , hard
5106 Viola Lime
19 Lime
29 Dolo. & sandy shale
33 " " "
49 Shale, green
55 Shale
62 Shale, green
65 Sand & pyrite
74 Lime
5202 Shale, green
15 Sand & shale
22 Shale
25 Shale, green
5248 Lime, Silicious
Total Depth.

Hole plugged back with 3 sacks of cement at bottom of liner and bridged at top of liner (4960') with plug & rocks and dumped 25 sacks of cement. Top of cement 4884. 63' of the bottom of 7" filled with cement.

Bailed dry and ripped 7" casing from 4690 to 4710. Hole showed some rotary mud after ripping. Ripped 7" from 4710 to 4720. Ripped from 4685 to 4715. Hole showed about 1/3 barrel of salt water and a rainbow in 5 hrs. Ripped 7" from 4660 to 4670. Hole showed 8 gal. water in 8 hours.

Pulled 3255 ft. 8 in. of 7" O.D. Casing.

Filled hole with mud up to bottom of surface pipe. Dumped 11 sacks of cement which filled hole 15 ft. Filled to 3 ft. of top with heavy mud and capped with 3 sacks of regular cement.

Plugging completed 12-13-37

PLUGGING

FILE SEC. 27-32-14W

BOOK PAGE 120 LINE 14

I hereby certify that the above is a true and correct copy of the log of J. C. Elsea # 1, SW SE NW/4, Sec. 27-32S-14W, Barber County, Kansas

C. L. Barnett

CASING RECORD

13"	O.D.	40#	L.W.	213
7"	O.D.	24#	S.S.	4943
5 1/8"	O.D. Liner			276' 9"
	Pulled Approx.			61'

SAND RECORD

Top of Mississippi Lime	4665
" Viola	4970
" Simpson	5115
" Silicious	5225
Total Depth	5248

Subscribed and sworn to before me
this 17th day of December, 1937

J. J. Bryant
Notary Public

My commission expires 4/20/38