


15-007-20228-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
214 N. Broadway P.O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above Section Plat

Barber County. Sec. 23 Twp. 32S Rge. (X) 14 (W)
Location as "NE/CNW/SW" or footage from lines c SW SW
Lease Owner Bowers Drilling Company, Inc. and Anadarko Production Co.
Lease Name Elsea "B" Well No. 1
Office Address 125 N. Market - Suite 1425, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 2 19 73
Application for plugging filed March 2 19 73
Application for plugging approved March 2 19 73
Plugging commenced March 2 19 73
Plugging completed March 2 19 73
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein, Attica, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4565 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	929'	8 5/8"	929'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


Plug: 300' w/25 sacks cement
40' w/10 sacks cement
2 sacks cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION
MAR 8 1973
3-5-73
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Hellar Drilling Company, Inc.
Address 339 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
D. L. Hellar, President of Hellar Drlg. Co. (Employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is filed and that the same are true and correct. So help me God.

(Signature) D. L. Hellar D. L. Hellar, President
339 Union Center Bldg., Wichita, Kansas 67202
(Address)



SUBSCRIBED AND SWORN to before me this 7th day of March, 19 73
Catherine Darcey
Catherine Darcey - Notary Public.

My commission expires March 25, 1976.

DRILLER'S LOG

COMPANY: Bowers Drilling Company, Inc. and Anadarko Production Co.,
 125 N. Market - Suite 1425, Wichita, Kansas 67202
 CONTRACTOR: Hellar Drilling Company, Inc., Wichita, Kansas 67202
 LEASE: #1 Elsea "B"
 LOCATION: c SW SW 23-32S-14W, Barber County, Kansas
 COMMENCED: February 11, 1973
 COMPLETED: March 2, 1973
 CASING: Set 8 5/8" Surface Casing @ 929' w/600 sacks cement

0-667	Surface Soil - Sand & Red Bed
667-929	Shale
929-1395	Shale & Red Bed
1395-1876	Shale & Red Bed & Salt Section
1876-2057	Shale & Lime
2057-2370	Lime & Shale
2370-2700	Ft. Riley
2700-2855	Lime
2855-3205	Lime & Shale Streaks
3205-3219	Shale
3219-3350	Shale & Lime
3350-3525	Lime & Shale (Topeka)
3525-3695	Lime & Shale
3695-3825	Shale
3825-3860	Lime & Shale
3860-4160	Lime
4160-4292	Lime (L.K.C.)
4292-4485	Lime
4485-4525	Lime & Chert (Marmaton & Miss.)
4525-4565	Lime
4565	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 8 1973
 3-8-73
 CONSERVATION DIVISION
 Wichita, Kansas

D & A

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Elsea "B", located in c SW SW 23-32S-14W, Barber County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*
 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 7th day of March, 1973.

Catherine Darcey
 Notary Public - Catherine Darcey

My Commission Expires:
 March 25, 1976.

