

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-22,025-0000

LEASE NAME Hinz B

WELL NUMBER 1-23

530 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 23 TWP. 32 RGE. 14 ~~W~~ or (W)

COUNTY Barber

Date Well Completed 5-10-85

Plugging Commenced 5-11-85

Plugging Completed 5-11-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P. O. Box 947, Pratt, Kansas 67124

PHONE# (316) 672-7581 OPERATORS LICENSE NO. 5087

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4855

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	311	8 5/8"	5-2-85	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged well with 125 sxs 60/40 poz, 3% A-7, 2% gel as follows: 750'-50 sxs; 330'-40 sxs; 40'-10 sxs with bridge plug; rathole-15 sxs; mousehole-10 sxs. Job by B. J. Titan Services. Plug down at 5:30 a.m. on May 11, 1985.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149

Address P. O. Box 329, Pratt, Kansas 67124


STATE OF Kansas COUNTY OF Pratt, ss.

Arnie Little

(Employee of Operator) or Conservation Division
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) Arnie Little

(Address) P. O. Box 329, Pratt, Kansas 67124



SUBSCRIBED AND SWORN TO before me this 17th day of May, 1985

Mary L. Tjaden
Notary Public

My Commission Expires: 3/22/88



- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

Oilfield Services, Inc. 15-007-22025-0000

DRILLER'S WELL LOG

Hinz B #1-23
200' N of C S/2 S/2 SE Sec. 23-32S-14W
Barber County, Kansas
Commenced: 5-1-85
Completed: 5-11-85
API #15-007-22,025
Operator: Texas Energies, Inc.

Depth		Formation	Remarks
From	To		
0	1033	Red Bed	Ran 7 joints (301') new, 24#, 8 5/8" surface casing. Set at 311' with 150 sxs Lite, 3% cc and 100 sxs Common, 2% gel 3%cc. Cement did circulate. Job by Halliburton. Plug down at 5:15 a.m. on May 2, 1985.
1033	1408	Red Bed, Shale	
1408	1873	Red Bed	
1873	2700	Shale	
2700	4855	Lime, Shale T.D.	

RTD 4855'

Plugged well with 125 sxs 60/40 poz, 3% A-7, 2% gel as follows: 750'-50 sxs; 330'-40 sxs; 40'-10 sxs with bridge plug; rathole 15 sxs; mousehole-10 sxs. Job by B J-Titan Services. Plug down at 5:30 a.m. on May 11, 1985. State Plugger out of the Dodge City, Kansas Office.

STATE OF KANSAS)
COUNTY OF PRATT) ss

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.


WHEATSTATE OILFIELD SERVICES, INC.

Arnie Little
ARNIE LITTLE, VICE-PRESIDENT

Mary L. Tjaden
NOTARY PUBLIC

My Commission Expires:

3/22/88



RECEIVED
STATE CORPORATION COMMISSION

5-20-85

MAY 20 1985

P.O. Box 329 • N. Highway 281 at Airport • Pratt, Kansas 67124 • Telephone (316) 672-7514

CONSERVATION DIVISION
Wichita, Kansas