

API NUMBER 15-007-21,578-0000

LEASE NAME Hinz 'C'

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1-22

220' FNL & 390' FWL SE/4

2420 Ft. from S Section Line

2250 Ft. from E Section Line

SEC. 22 TWP. 32SRGE. 14 (X) or (W)

COUNTY Barber

Date Well Completed 05-27-83

Plugging Commenced 12-05-89

Plugging Completed 12-28-89

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P.O. Box 947 Pratt, KS 67124

PHONE# (316) 672-8514 OPERATORS LICENSE NO. 5087

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-04-89 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Mississippi Depth to Top 4586 Bottom 4590 T.D. 4684

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				16	60	None
				8 5/8	1020	None
				4 1/2	4678	3790

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set cast iron bridge plug at 4483', dumped 2 sxs cement on top, pulled 4 1/2" casing. Pumped down 8 5/8" casing as follows: 24 bbls, fresh water with 500# hulls, 145 sxs 65% Class A cement with 35% pozmix A 10% gel mixed at 12.3#/gal. Max. press. 500#, ISIP 350#. Ran slickline, found top of cement at 325'. Filled to surface with approx. 4.3 cubic yards of readymix cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Texas Energies, Inc. License No. 5087

Address P.O. Box 947 Pratt, KS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Texas Energies, Inc.


STATE OF Kansas COUNTY OF Pratt, ss.

Mark P. Stevenson (Employee of Operator) or OPERATOR of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mark P. Stevenson

(Address) P.O. Box 947 Pratt, KS 67124



AND SWORN TO before me this 8th day of January, 19 90

Julia Berry
 Notary Public

My Commission Expires: Feb. 6, 1993

ORIGINAL