


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barber County, Sec. 22 Twp. 32 Rge. 14 W (W)  
Location as "NE/CNW/SW" or footage from lines C NW SE  
Lease Owner Petroleum, Inc.  
Lease Name Elsea "C" Well No. 1  
Office Address Route 2, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed April 14 19 57  
Application for plugging filed April 14 19 57  
Application for plugging approved April 14 19 57  
Plugging commenced April 14 19 57  
Plugging completed April 14 19 57  
Reason for abandonment of well or producing formation No Producing zones

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production None 19       
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives Pratt, Kansas  
Producing formation --- Depth to top -- Bottom -- Total Depth of Well 4670 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	289'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

Mud up to 275' with heavy mud pushed down 1/4 sack hulls to 275' followed by wooden plug. Placed 20 sacks cement through drill pipe on to plug. Mud up to 40' and placed 1/2 sack hulls at 40' followed by wooden plug and 10 sacks cement to base of well cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Co.  
Address Route 2, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Don Searle (employee of owner) or (owner of operation) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle  
Route 2, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of April, 19 57

My commission expires July 11, 1960

Ed Brown  
Notary Public.  
4-25-57  
APR 25 1957

CONSERVATION DIVISION  
Wichita, Kansas  
PLUGGING  
FILE SEC. 22 T. 32 R. 14 W  
BOOK PAGE 6 LINE 19

15-007-00392-0000  
WELL LOG

COMPANY PETROLEUM, INCORPORATED

SEC. 22 T. 32S R. 14W

FARM ELSEA 'C' NO. 1

LOC. Approx. C/NW, SE


TOTAL DEPTH 4670'

COUNTY Barber Co., Kansas

COMM. March 28, 1957

COMP. April 14, 1957

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 289' W/225 sax.

ELEVATION 1832' DF

PRODUCTION D & A.

FIGURES INDICATE BOTTOM OF FORMATIONS

880	Red rock & gyp	Heebner	3881'
1400	Red bed	Douglas	3948
1425	Gyp & shale	Lansing	4061
2040	Lime & shale	Base K. C.	4468'
2235	Lime	Lansing	4061
2345	Shale & lime	Miss.	4570
2420	Sand & shale		
2630	Lime & shale W/sand		
3935	Shale & lime		
4063	Shale		
4175	Lime		
4216	Lime & shale		
4481	Lime		
4528	Lime & shale		
4565	Lime		
4590	Chert		
4670	Lime & chert		
4670	T. D.		

State of KANSAS }  
County of BARTON } ss:

PLUGGING  
FILE SEC 22 T 32 R 14W  
BOOK PAGE 6 LINE 19

I, Verne A. Morris of Garvey Drilling Co.

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Elsea 'C' well

RECEIVED  
STATE CORPORATION COMMISSION  
Verne A. Morris

Subscribed and sworn to before me this 23rd day of April

19 57 APR 25 1957  
4-25-57

My Commission Expires: July 11, 1960

CONSERVATION DIVISION  
John A. Brown  
NOTARY PUBLIC