

CPI

15-135-19094-0000

# PHILLIPS PETROLEUM COMPANY

**PLUGGING**  
 FILE SEC-13-T-18-R-21W  
 BOOK PAGE-6-LINE-29

Wichita, Kansas,  
 June 19, 1935.

**RECEIVED**  
 JUN 20 1935  
 BY *mc*

Mr. T. A. Morgan, Director,  
 Proration Division,  
 Kansas State Corporation Commission,  
 800 Bitting Building,  
 Wichita, Kansas.

Dear Sir:

Application is hereby made to plug our A. R. Young well No. 1 located in the SW/4 of Section 13-18S-21W, Ness County, Kansas.

This well was drilled to a TD of 4235 feet, and was found to be non-productive.

We desire to plug this well in the following manner:

Place a cement plug from 4210' to 4150'; pull the 7" casing; place another cement plug from 3650' to 3500'. This will bring the cement to the bottom of the 8", which we will then pull, and mud back to the top of the hole and fill over.

The 12 $\frac{1}{2}$ " is set at 1450' and is cemented from top to bottom. This pipe, of course, will be left in the hole. Also, the 15 $\frac{1}{2}$ " set at 600', which is cemented from top to bottom, will be left in the hole.

Your prompt approval of this request will be very much appreciated.

Yours very truly,

PHILLIPS PETROLEUM COMPANY

*C. E. Klein*  
 C. E. KLEIN

TAW:GRM

**PLUGGING**  
FILE SEC. 13 T. 18 R. 21W  
BOOK PAGE 2 LINE 2

15-135-19094-0000

June 20, 1935.

Plugging A.R. Young No. 1  
SW $\frac{1}{4}$  13-18-21W  
Ness County  
6-29

Phillips Petroleum Co.,  
Ellis-Singleton Bldg.,  
Wichita, Kansas.

Attention: C. E. Klein

Dear Sirs:

This letter is your authority to plug the above subject well, in accordance with the rules and regulations of the State Corporation Commission.

Yours very truly,

T. A. MORGAN, Director

TC:ha

By