

15-007-30254-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 10 1965
11-10-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Eason Oil Company

Complete Address: Box 9755, Oklahoma City, Oklahoma

Lease Name Allen Well No. # 1-33

Location C NE Sec. 33 Twp. 32 Rge. 14 (E) (W) W

County Barber Total Depth 5065'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Gayle E. Toland

Address: Box 94366, Oklahoma City, Oklahoma License No. 539

Operation Completed: Hour 12:30PM Day 8th Month Nov. Year 1965

The Above well was plugged as follows:

250' of 13 3/8" surface pipe, cement circulated. 2350' of 8 5/8" surface
pipe, cemented with 150 sacks. 1787' of 8 5/8" surface pipe was recovered
from the hole. Hole was filled with mud to 250', rock bridge from 250' to
240', and cemented with 4 yards of ready-mix cement. Hole was filled with
mud to 40', rock bridge from 40' to 30', and cemented with 2 yards of
ready-mix cement to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11/10/65
INV. NO. 2161-4