

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 16 1964
6-16-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Beardmore Drg Co
Complete Address: 827 Beacon Bldg Wichita, Kans
Lease Name Wunder Well No. 1
Location CSE SW Sec. 18 Twp. 18 Rge. (E) (W) 21
County Ness Total Depth 4243
Abandoned Oil Well x Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Knight Casing Pulling Co & Halliburton Co
Address: Chase, Kans License No. 436
Operation Completed: Hour 2:30PM Day 13 Month 6 Year 64

The Above well was plugged as follows:

8 5/8" 180' with 100 sax cement - 5 1/2" 4236' with 125 sax cement - hole in 5 1/2" in Dakota section - well flowing from Cheyenne.

Set 2" tubing - pumped 25 sax cement in bottom through 2" tubing - mudded hole with gel and weight mud to kill water flow - cementing and mudding by Halliburton Co.

Pulled 2890' 5 1/2" to 640' - circulated hole with heavy mud through 5 1/2" - displaced 20 sax cement through 5 1/2" at 640' - heavy mud to 320' - displaced 20 sax cement through 5 1/2" at 320' - heavy mud to 35' - cement 35' to bottom cellar - cementing and mudding by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Leon Petty*
Well Plugging Supervisor

DATE 6/16/64
INV. NO. 9315-41