

15135-20371-0000

Form CP-3
Rev. 6-4-68

KANSAS

10
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 22 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company & Southwest Petro - Chem.
Complete Address 705 Fourth National Bank Bldg., Wichita, Kansas
Lease Name Goede "C" Well No. 1
Location C SE SE Sec. 17 Twp. 18 Rge. (E) (W) 21
County Ness Total Depth 4265
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 12 N Day 20 Month 10 Year 1970

The above well was plugged as follows:

RTD 4265' 8 5/8 csg set at 275' cwc Cmt. Mat. 100 sk poz 6% gel.
Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ben F. Massey
Well Plugging Supervisor

DATE 10/22/70
INV. NO. 2729-W