

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-01446-00-00  
Spot: SENENW Sec/Twnshp/Rge: 25-32S-14W  
4290 feet from S Section Line, 3630 feet from E Section Line  
Lease/Unit Name: ELSEA B Well Number: 1  
County: BARBER Total Vertical Depth: 4919 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S. MARKET  
WICHITA, KS 67202

Production Casing Size: 2.875 feet: 4915 WITH 150 SX CMT  
Surface Casing Size: 10.75 feet: 240 WITH 150 SX CMT

Well Type: EOR UIC Docket No: E09524.1 Date/Time to Plug: 07/25/2003 1:45 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: RICHARD LACEY Company: KANSAS CORPORATION COMMIS Phone: (620) 225-8888

Proposed Plugging Method: PUMP 20 SX CMT DOWN 2 7/8" CASING. FREEPOINT & RECOVER CASING. PUMP PLUGS THROUGH CASING. 600' WITH 20 SX GEL - 75 SX CMT. 270' WITH 75 SX CMT. 40' WITH 20 SX CMT. CUT OFF CASING & RESTORE LOCATION.

Plugging Proposal Received By: RICHARD LACEY

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 07/25/2003 3:30 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 4870-4875'. PUMPED DOWN 2 7/8" CASING WITH 20 SX CMT. TOP OF PLUG AT 4100'. SHOT 2 7/8" CASING OFF AT 2000'. NOT FREE. SHOT OFF AT 620'. NOT FREE. TOOK INJECTION RATE @ 3 1/2 BPM @ 400#. 1ST PLUG PUMPED DOWN 2 7/8" CASING WITH 20 SX GEL & 75 SX CMT. SHOT OFF 2 7/8" CASING AT 280'. LAY DOWN 1 JOINT. 2ND PLUG AT 250' WITH 10 SX GEL & 75 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT


RECEIVED

AUG 08 2003  
8-8-03  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 280' OF 2 7/8" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer  
(TECHNICIAN)

[Signature]  
Form CR-276