

To: 1 040330
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-f 21482-0000
API NUMBER 15- 007-21,382

C N/2 N/2, SEC. 31, T 32 S, R 14 W/EX

4620 feet from S section line

2640 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6769

Lease Name Cline-Mills Well # 2

Operator: Farrar Pump & Supply Company, Inc.

County Barber 156.72

Name &

Address P.O. Box 209

Well Total Depth 4822 feet

Medicine Lodge, KS 67104

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 307

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10:45 a.m. Day: 4 Month: 10 Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4780' Perforated at 4286' (one shot)

1st plug sand back to 4230' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 09 1989

10-7-89

Plugging Proposal Received by Steve Pfeifer

Wichita, Kansas

(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 11:30 a.m. Day: 4 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sand back to 4220' and dumped 4 sx cement on top of sand bridge with bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 100 sx cement.

Maximum pressure 200 psi and shut in 150 psi.

Pumped through 2" collar welded into 8 5/8" surface pipe.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1440' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-11-89

INV. NO. 26082

Signed

Stephen J. Pfeifer
(TECHNICIAN)