

1 040329

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-f 15-007-20132-0000
API NUMBER 15- Drill Completion Date 1/15/70

C NW SW, SEC. 31, T 32 S, R 14 W/E
1980 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3399

Lease Name Cline-Mills Well # 1

Operator: Farrar Pump & Supply Company, Inc.
Name & Address

County Barber 155.55

P.O. Box 209
Medicine Lodge, KS 67104

Well Total Depth 4786 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 12:15 p.m. Day: 4 Month: 10 Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4786' PRTD 4797' Perfs at 4278, 4646-49'

1st plug sand back to 4250' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, 100 lbs. wiper plug and pump 100 sx cement.

OCT 09 1989

10-9-89
STATE CORPORATION COMMISSION
WICHITA, KANSAS

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1 p.m. Day: 4 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4220' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 200 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2420' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 10-11-89

Signed Stephen J Pfeifer (TECHNICIAN)

INV. NO. 26081