

1 040533

4-30  
API NUMBER 15- 007-20,915 -0000

418 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

E/2 NE SE, SEC. 29, T 32 S, R 14 W/4E

1980 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5476

Lease Name Cline Well # 1

Operator: DNB Drilling

County Barber 139.06

Name & Address P.O. Box 8877

Well Total Depth 4279 feet

Wichita, KS 67202-4224

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 212

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11:30 a.m. Day: 30 Month: 4 Year: 19 91

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4277' w/75 sx cement. Perfs at 4243-41'

1st plug sand back to 4190' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

5-6-91  
MAY 06 1991

Plugging Proposal Received by Richard Lacey

(TECHNICIAN) CONSERVATION DIVISION  
Wichita, Kansas

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:15 p.m. Day: 30 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4190' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 300 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3100' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED (If applicable) observe this plugging.

DATE 5-9-91

INV. NO. 31780

Signed *Stephenson R. Pfeiffer*  
(TECHNICIAN)