

1040939

2-21

API NUMBER 15- 007-21,658 -0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION App.  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C NE NW, SEC. 1, T 32 S, R 15 W/E

4860 feet from S section line

3290 feet from E section line

Lease Name Alexander Well # 1

County Barber

Well Total Depth 5064 164.58 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 337

TECHNICIAN'S PLUGGING REPORT

Operator License # 30931

Operator: Daystar Petroleum Inc.

Name

Address 1321 W. 93rd N.

Valley Center, KS 67147

Abandoned Oil Well Gas Well  Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 9:30 a.m. Day: 21 Month: 2 Year: 1995

Plugging proposal received from Alan Vratil

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4224' w/175 sx cement, PBD 4224', Perfs at 4045-47'

1st plug sand back to 4000' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part None

Operations Completed: Hour: 10 a.m. Day: 21 Month: 2 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 3980' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 600 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
(if additional description is necessary, use BACK of this form.) observe this plugging.

DATE 2-27-95

INV. NO. 42280

Signed *Steve Pfeifer* (TECHNICIAN)

STATE CORPORATION COMMISSION  
RECEIVED  
2-24-95  
FEB 24 1995