

1070018

15-087-16625-0000

API NUMBER 15- 7/27/60-Drill date

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

SE SE SE, SEC. 24, T 32 S, R 14 W/E

330 feet from S section line
330 feet from E section line

4-12

TECHNICIAN'S PLUGGING REPORT
Operator License # 5144

Lease Name Elsea Well # 2

Operator: Mull Drilling Company, Inc.
Name & Address: P.O. Box 2758
Wichita, KS 67201

County Barber
Well Total Depth 4870 158.27 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 966

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 12 Month: 4 Year: 1996

Plugging proposal received from Mike Kelso

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2537

Work: 5 1/2" at 4854' w/150 sx cement, PBSD 4542', Perfs at 4843-51, 4539-54', CIBP @ 4579'.
1st plug sand back to 4440' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:55 a.m. Day: 12 Month: 4

ACTUAL PLUGGING REPORT 1st plug ran wireline to 4500'. Sanded back to 4440' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 100 sx cement.

Maximum pressure 0 psi and shut in 0 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2000' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed *[Signature]* (TECHNICIAN)

KANSAS RECEIVED APR 18 1996

INVOICED

DATE APR 18 1996

INV. NO. 45356