

1040950

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-01,045 -00-01

C SW NE, SEC. 11, T 32 S, R 14 W EX

3300 feet from S section line

1980 feet from E section line

Lease Name Lake Well # 1 OWWO

County Barber 143.36

Well Total Depth 4411 feet

Conductor Pipe: Size feet

Surface Casing: Size 13 3/8 feet 200

TECHNICIAN'S PLUGGING REPORT

Operator License # 5255

Operator: McGinness Oil Co.

Name & Address 1025 Union Ctr. Bldg.

Wichita, KS 67202

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Hardtner Well Service License Number 30607

Address 150 N. Main, Ste. 1026, Wichita, KS 67202

Company to plug at: Hour: 8 a.m. Day: 8 Month: 4 Year: 19 95

Plugging proposal received from Doug McGinness

(company name) McGinness Oil Co. (phone) 316-267-6065

were: 5 1/2" at 4391' w/225 sx cement, PBD 4370', Perfs at 4111-13, 3931-37, 3856-59'

Bridge plugs at 4071' and 3900'

1st plug set CIBP at 3840' and dump 2 sx cement on top of CIBP through bailer,

2nd plug pump down 13 3/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 175 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 8:45 a.m. Day: 8 Month: 4 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3840' and dumped 2 sx cement on top through bailer,

2nd plug pumped down 13 3/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 175 sx cement.

Maximum pressure 275 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3027' of 5 1/2" casing  
(If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION  
APR 14 1995  
CONSERVATION DIVISION  
WICHITA, KANSAS

INVOICED

observe this plugging.

Signed Steve Pfeifer  
(TECHNICIAN)

DATE 4-26-95

WELL NO. 42698



