

1 080465

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,739-08-01  
275' E & 100' S of  
NW NW SW, SEC. 36, T 32 S, R 14 W/X  
275' E & 100' S of  
2310 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087  
Operator: Texas Energies, Inc.  
Name & Address P. O. Box 947  
Pratt, KS 67124

Lease Name Hinz Well # 1-36  
County Barber 164.94  
Well Total Depth 5075 feet  
Conductor Pipe: Size 16" feet 45  
Surface Casing: Size 8 5/8 feet 1112

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:45 pm Day: 27 Month: December Year: 19 85

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4900' PBD 4855' Perfs at 4709-4715' Elevation 1944' GL 1957 KB  
1st plug sand back to 4660' and dump 4 sx cement on top of sand through bailer  
2nd plug squeeze well with 3 sx hulls, 50 sx cement, 8 sx gel, release 8 5/8" rubber plug, and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 3:30 pm Day 27 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4660' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 50 sx cement, 8 sx gel, released 8 5/8" rubber plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 200 psi

Remarks: Recovered 3818' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Halliburton.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE JAN 06 1986  
INV. NO. 11854

JAN 2 1986  
1-2-86  
CONSERVATION DIVISION

Signed J. A. [Signature] (TECHNICIAN)