

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21015-00-00
Spot: E2W2SW Sec/Twnshp/Rge: 35-32S-14W
1320 feet from S Section Line, 990 feet from W Section Line
Lease/Unit Name: HULL E Well Number: 1
County: BARBER Total Vertical Depth: 4783 feet

Operator License No.: 5506 Conductor Pipe: Size feet:
Operator Name: WOOLSEY PETROLEUM CORPOR Surface Casing: Size 8.625 feet: 412
Address: 125 N. MARKET, SUITE 1000 Production: Size 2.875 feet: 4750 *155.45*
WICHITA, KS 67202 *9/28* Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 09/28/2000 9:50:00 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: ALAN DICK Company: WOOLSEY PETROLEUM Phone: (316) 886-5606

Proposed Plugging Method: CUT CSG. @ FREE POINT. PUMP 25 SX CMT. PULL CSG TO 600' & PUMP 50 SX. PULL CSG TO 442' & PUMP 50 SX. PULL CSG TO 30' & PUMP CMT TO SURFACE.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/28/2000 10:50 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

OPEN HOLE AT 4750-83, CIBP @ 4730, 4678-84, CIBP @ 4668, 4624-34, CIBP @ 4610, 4470-76, CIBP @ 4450, 4086-92. CIBP @ 4020'. LOAD HOLE WITH DRILLING MUD. 1ST PLUG AT 560' WITH 50 SX CMT. 2ND PLUG AT 420' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. GOOD CIRCULATION THROUGHOUT JOB.

RECEIVED
STATE CORPORATION COMMISSION
OCT 3 2000
10-3-00
CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 560' OF 2 7/8" TUBING.

Plugged through: TBG

District: 01

Signed

[Signature]
(TECHNICIAN)

INVOICED
DATE 10/4/00
INV. NO. 2001060786

OCT 02 2000
MP

Form *[Signature]* 6823