

1 120482

10-11

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22, 138 ~~7889~~

NW NW SE SW SEC. 18, T 18 S, R 21 W/E

App. 1140 feet from S section line

App. 3780 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4058

Lease Name Wunder "B" Well # 2

Operator: American Warrior, Inc.

County Ness 137.96

Name & Address Box 399

Well Total Depth 4245 feet

Garden City, KS 67846

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 11 Month: 10 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4236' w/125 sx cement, Open hole at 4236-45', Perfs at 4142-46, 4149-52'

1st plug sand back to 4090' and dump 5 sx cement on top of sand through bailer,
shoot casing at 1430' (Anhydrite),
2nd plug pump 75 sx cement, 200 lbs. hulls, and 140 sx cement.

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 11 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4090' and dumped 5 sx cement on top of sand through bailer,

2nd plug perforated 5 1/2" casing at 1430' and pumped 75 sx cement, 300 lbs. hulls and 145 sx cement.

Pumping pressure 0-500 psi and shut in 200 psi.

5 1/2" casing had been squeezed with cement and cement is visible in the bradenhead.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE 10-22-90

INV. NO. 29684

OCT 17 1990
10-17-90
CONSERVATION DIVISION
Wichita, Kansas

Signed Ronan Rankin (TECHNICIAN)