

10-11

1 120481

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-21,978-~~0000~~
150' N & 150' W

SE SE SW, SEC. 18, T 18 S, R 21 W/E

480 feet from S section line

3120 feet from E section line

Lease Name Wunder "B" Well # 1

County Ness 137.99

Well Total Depth 4246 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 263

TECHNICIAN'S PLUGGING REPORT

Operator License # 4058

Operator: American Warrior

Name & Address: Box 399

Garden City, KS 67846

Abandoned Oil Well Gas Well Input Well SMD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10:30 a.m. Day: 11 Month: 10 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4239' w/125 sx cement. Open hole 4239-45', Perfs at 4141-45'

1st plug sand back to 4090' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 75 sx cement, 200 lbs. hulls, and 100 sx cement.

Perforate 4 1/2" casing at 1430'.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12 p.m. Day: 11 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4090' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 4 1/2" casing with 75 sx cement, 300 lbs. hulls, and 100 sx cement.

Perforated 4 1/2" casing at 1427'.

Pumping pressure 0-600 psi and shut in 50 psi.

4 1/2" casing had been squeezed with cement and cement is visible in the bradenhead.

Remarks: Used 60/40 Pozmix 6% gen. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-22-90

WV. NO. 29685

OCT 17 1990
10-17-90
CONSERVATION DIVISION
Wichita, Kansas

Signed Duane Rankin (TECHNICIAN)