

1060168

8-13

TO: STATE CORPORATION COMMISSION 120'S 50'W E/2 W/2 SE SEC. 14, T 18 S, R 21 W API NUMBER 15-135-24,078-0000

CONSERVATION DIVISION - PLUGGING SECTION 1200 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1700 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME WELLS K WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY NESS

OPERATOR LICENSE # 4058 WELL TOTAL DEPTH 2336 75.92 FEET

OPERATOR: AMERICAN WARRIOR, INC. PRODUCTION CSG: SIZE " FEET

NAME AND PO BOX 399 SURFACE CASING: SIZE 8 5/8" @ 222' WITH SX

ADDRESS GARDEN CITY, KS 67846

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DISCOVERY DRILLING, INC LICENSE NUMBER 31548

ADDRESS PO BOX 763, HAYS, KS 67601

COMPANY TO PLUG AT: HOUR: 11:00 PM DAY: 12 MONTH: 08 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM TOM

(COMPANY NAME) DISCOVERY DRILLING, INC (PHONE) 785-623-2920

WERE:

1ST PLUG AT 1400' WITH 50 SX CEMENT, 2ND PLUG AT 650' WITH 40 SX CEMENT,

3RD PLUG AT 230' WITH 40 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT,

5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,

NO MOUSE HOLE.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 1:30 AM DAY: 13 MONTH: 08 YEAR: 1999

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 1400' WITH 50 SX CEMENT, 2ND PLUG AT 650' WITH 40 SX CEMENT,

3RD PLUG AT 230' WITH 40 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT,

5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,

NO MOUSE HOLE.

CONSERVATION DIVISION

REMARKS: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

DATE 8-31-99

SIGNED Michael J. Maier (TECHNICIAN)

FORM CP-213

INV. NO. 60445

Handwritten signature and initials in a circle.

Stamp: RECEIVED STATE CORPORATION COMMISSION AUG 31 1999 8-30-99

INVOICED