

121042

6-21

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-21,729-0001

SE NW NW, SEC. 13, T 18 S, R 21 W/E  
990 feet from N/S section line  
990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4058

Lease Name Young Well # 1 OWWO

Operator: American Warrior, Inc.

County Ness

Name & Address P.O. Box 399

Well Total Depth 2600 84.50 feet

Garden City, KS 67846

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 322

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Southwest Well Service License Number 4058

Address

Company to plug at: Hour: 5 p.m. Day: 21 Month: 6 Year: 19 95

Plugging proposal received from Scott Corsair

(company name) American Warrior, Inc. (phone) 913-398-2270

Work: CIBP at 2350', Perfs at 2238-90', Originally drilled in 1979 w/4 1/2" casing set at 4214' w/150 sx cement, 350 sx pumped in annulus  
1st plug fill 4 1/2" casing with cement and squeeze with cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 6:30 p.m. Day: 21 Month: 6 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug ran tubing to 2200' and pumped 50 sx cement,

2nd plug pulled tubing to 1000' and circulated cement with 125 sx.

3rd plug squeezed in 4 1/2" casing with 75 sx cement. Shut in with 1000 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
6-29-95  
JUN 29 1995

Remarks: Used 65/35 Pozmix 8% gel by HOWCO. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 6-30-95

Signed Deann Rankin (TECHNICIAN)

INV. NO. 43011  
6-21 AUG 31 1995

EFFECTIVE DATE: 11-6-94

State of Kansas

135-21,729-00-01

FORM MUST BE SIGNED

DISTRICT #

NOTICE OF INTENTION TO DRILL

ALL BLANKS MUST BE FILLED

SGA7 Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 11 04 94 month day year

Spot SE NW NW Sec 13 Twp 18 S, Rg 21 East West

OPERATOR: License # 4058 Name: American Warrior, Inc Address: P.O. Box 399 City/State/Zip: Garden City, Ks 67846 Contact Person: Scott Corsair Phone: 913-398-2270

990 feet from 2005 / North line of Section 990 feet from 2005 / West line of Section

IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

County: Ness

Lease Name: Young Well #: 1 OWWO

Field Name: Elmore SW

Is this a Prorated/Spaced Field? yes X no

Target Formation(s): Cherokee

Nearest lease or unit boundary: 990'

Ground Surface Elevation: 2144 feet MSL

Water well within one-quarter mile: yes X no

Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 400'

Depth to bottom of usable water: 550'

Surface Pipe by Alternate: 1 X 2

Length of Surface Pipe Planned to be set: 320'

Length of Conductor pipe required: NONE

Projected Total Depth: 4100'

Formation at Total Depth: Cherokee

Water Source for Drilling Operations:

well X farm pond other

DWR Permit #:

Will Cores Be Taken?: yes X no

If yes, proposed zone:

CONTRACTOR: License #: 4058 Name: Southwest Well Service

Well Drilled For: Well Class: Type Equipment: Oil Enh Rec Infield Mud Rotary Gas Storage Pool Ext Air Rotary X OWWO Disposal Wildcat Cable Seismic: # of Holes Other

If OWWO: old well information as follows: Operator: Euwer Petr. Co & Rains & Williamson Well Name: #1 Young Comp. Date: 3-27-80 Old Total Depth: 4215'

Directional, Deviated or Horizontal wellbore? yes X no

If yes, true vertical depth:

Bottom Hole Location:

Exp. 5/1/95

AFFIDAVIT

320' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

It is agreed that the following minimum requirements will be met:

RECEIVED STATE OF KANSAS

Pusher SPUD DATE 11-3-94 INIT. LR LENGTH SURFACE PLANNED RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE @ CONDUCTOR ANHYDRITE T- B- ELEVATION Pipe in hole TD FORMATION RAN PIPE @ DV TOOL ALT II DONE SX Y N Arbuckle Plug @ Ft. W/ SX Hug./Council @ Ft. W/ SX Anhydrite Base @ Ft. W/ SX 1/2 Base Anyh. @ Ft. W/ SX 1/2, 1/2 Plug @ Ft. W/ SX Bottom Surface @ Ft. W/ SX 40' Plug @ Ft. W/ SX RAT HOLE CIRC/W SX MOUSE HOLE W/ SX WATER WELL SX (Furr. Well Pond Hauling) TECHNICIAN DATE RECEIVED JUN 29 1995 TYPE OF CEMENT (AM/PM) DATE COMPLETION TIME (AM/PM) DATE CEMENT COMPANY

P. Longford 11-1-95