

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-21,729-0000
SE NW NW Sec. 13, T 18 S, R 21 W/4
_____ feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

_____ feet from W/E section line

Operator License # 5146

Lease Name Young Well # 1

Operator: Rains + Williamson Oil Co
Name & Address 435 Page Court,
220 Douglas
Wichita, KS 67202

County Ness
Well Total Depth 4215 feet 136.99
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rains + Williamson Oil Co License Number 5146

Address 435 Page Court 220 Douglas Wichita KS 67202

Company to plug at: Hour: 11:00 am Day: 1 Month: November Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Paul Stephans

(company name) Rains + Williamson (phone) 913-735-2215

were: To pump down 4 1/2" production casing with
150 sy of 60/40 pozmix 2% gel 3% cc. Also
check 8 5/8 annulas to see if cement was
to surface since company claimed hole
was squeezed from dakota to surface

Signed Don Ubel received plug
(TECHNICIAN) propose 1

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00 noon Day: 1 Month: November Year: 1983

ACTUAL PLUGGING REPORT Plugged down 4 1/2" casing with 150 sy
of 60/40 pozmix 2% gel 3% cc Had a maximum
pump pressure of 2000 psi. Shot in pressure
of 500 psi. Surface pipe annulas was standing
full of cement There is a Halliburton plug packer @ 3950
Dowell pumped the cement

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / ~~did not~~) observe this plugging.

INVOICED
DATE 11-21-83
INV. NO. 7013-W

RECEIVED
STATE CORPORATION COMMISSION
Signed Richard W. Lacey
NOV 3 1983 (TECHNICIAN)