

TS:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Operator: Ritchie Exploration, Inc.
Name & Address 125 North Market, Suite 1000
Wichita, KS 67202

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☒ X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 5 p.m. Day: 21 Month: 2 Year: 19 88

Plugging proposal received from Lloyd Delett

(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2128'
Anhydrite 1374-1405'

1st plug at 1380' with 50 sx cement, 2nd plug at 750' with 75 sx cement,

3rd plug at 300' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☐ Part ☐ None ☒ X

Operations Completed: Hour: 8:45 p.m. Day: 21 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1380' with 50 sx cement,

2nd plug at 750' with 75 sx cement,

3rd plug at 300' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (XXX) did not observe this plugging.

DATE 2-29-88

INV. NO. 19952
2-2/

2-21-88 R 151
API NUMBER 15- 135-23,219-0000

C SW SW, SEC. 21, T 18 S, R 21 W/E

660 feet from S section line

4620 feet from E section line

Lease Name Clarence Foos Well # 1

County Ness 139.07

Well Total Depth 4279 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 282

STATE CORPORATION COMMISSION

FEB 26 1988

2-26-88
CONSERVATION DIVISION
Wichita, Kansas

Signed Steve Durrant
(TECHNICIAN)

MAR 24 1988

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... 2/12/88
month day yearAPI Number 15-135-23,219-0000 2
C SW SW Sec. 21 Twp. 18 S, Rg. 21 X East
660 Ft. from South Line of Section
4620 Ft. from East Line of SectionOPERATOR: License # 4767
Name Ritchie Exploration, Inc.
Address 125 N. Market, Suite 1000
City/State/Zip Wichita, KS 67202
Contact Person Leah Ann Kasten
Phone 316/267-4375(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 660 feetCONTRACTOR: License # 6033
Name Murfin Drilling Co.
City/State Wichita, KSCounty Ness
Lease Name Clarence Foos Well # 1
Ground surface elevation est. 2128 feet MSLWell Drilled For: Well Class: Type Equipment:
X Oil Storage Infield X Mud Rotary
Gas Inj Pool Ext. Air Rotary
OWWO X Expl X Wildcat CableDomestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

If OWWO: old well info as follows:

Depth to bottom of fresh water 100
Depth to bottom of usable water 600Operator
Well Name
Comp Date Old Total DepthSurface pipe by Alternate: 1-2X
Surface pipe planned to be set 280
Conductor pipe required n/a

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Projected Total Depth 4300 feet
Formation Mississippian

Date 2/8/88 Signature of Operator or Agent Leah Ann Kasten Title Geologist

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X

This Authorization Expires 8-9-88 Approved By Peth 2-9-88

EFFECTIVE DATE: 2-14-88

8:50 AM Spud 12/24 3:00 PM

no water well

C SW SW Sec. 21 Twp. 18 S, Rg. 21 X East

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep.....1750	or formation with.....50 sacks	of. 60/40 pozmix, 6% gel.
2nd plug @ ft. deep.....970	or formation with.....80 sacks	of. " " "
3rd plug @ ft. deep.....310	or formation with.....50 sacks	of. " " "
4th plug @ ft. deep.....40	or formation with.....10 sacks	of. " " "
5th plug @ ft. deep.....	or formation with.....	feet of.....

(2) Rathole to surface minus 5 feet

(b) Mousehole to surface minus 5 feet

PUSHER Lloyd & Celeste

TD 4279 FORMATION Miss

SURFACE PIPE 8 7/8 @ 282

ANHYDRITE 1374 ELEVATION 2129

STARTING TIME & DATE 2-21-88 5:00 PM

COMPLETION TIME & DATE 2-21-88 8:45 PM

1st PLUG @ 1380 FT. W/ 50 SX

2nd PLUG @ 1750 FT. W/ 75 SX

3rd PLUG @ 300 FT. W/ 40 SX

4th PLUG @ 400 FT. W/ 10 SX

RAT HOLE CIRCULATED W/ 15 SX

MOUSE HOLE CIRCULATED W/ SX

WATER WELL PLUGGED W/ Hand SX

CEMENT COMPANY 6/4 60 allied

TECHNICIAN JF

RECEIVED
STATE CORPORATION COMMISSION

FEB 26 1988

CONSERVATION DIVISION
Wichita, Kansas