

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

11-11

API NUMBER: 15-155-21,366-0000  
NW,NW,NW, SECTION 30 TOWNSHIP 24 RANGE 10W

OPERATOR LICENSE # 3180

330 FEET FROM 8 SECTION LINE  
330 FEET FROM 2 SECTION LINE

OPERATOR DEUTSCH OIL COMPANY  
NAME & 107 N. MARKET #1115  
ADDRESS WICHITA, KS 67202

LEASE NAME: HAYES #1-30  
COUNTY: RN Reno  
WELL TOTAL DEPTH: 3865' 125.61

PIPE: NONE

SURFACE CASING: 8 5/8" @ 263'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_  
PLUGGING CONTRACTOR: DUKE DRILLING  
ADDRESS: 310 W. CENTRAL #202, WICHITA, KS 67202 LICENSE: 5929

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: 11 MONTH: 11 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: DISTRICT #2  
COMPANY NAME: ALLIED CEMENTING PHONE: 316-793-5861


WERE: RUN TUBING TO 1450' AND SPOT 35 XS. CMT. PULL TUBING TO 900' AND SPOT 35 XS. CMT. PULL TUBING TO 315' AND SPOT 35 XS. CMT. PULL TUBING TO 60' AND SPOT 25 XS. CMT. SPOT 15 XS. CMT. IN RAT HOLE AND 10 XS. CMT. IN MOUSE HOLE.

PLUGGING PROPOSAL RECEIVED BY: JOHN ARMBRUSTER  
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: \_\_\_\_\_ DAY: 11 MONTH: 11 YEAR: 1995  
ACTUAL PLUGGING REPORT:

RAN TUBING TO 1450' AND SPOTTED 35 XS. CMT. PULLED TUBING TO 900' AND SPOTTED 35 XS. CMT. PULLED TUBING TO 315' AND SPOTTED 35 XS. CMT. PULLED TUBING TO 60' AND SPOTTED 25 XS. CMT. SPOTTED 15 XS. CMT. IN RAT HOLE. SPOTTED 10 XS. CMT. IN MOUSE HOLE.

REMARKS: ALLIED #2875. 155 XS. CMT. 60/40 POZ. 4% GEL.  
I DIDNOT OBSERVE THIS PLUGGING.

  
\_\_\_\_\_  
Jerry Clark (AGENT)

RECEIVED FORM CP-2/3  
KANSAS CORPORATION COMMISSION REV: 3/3/90

NOV 17 1995

CONSERVATION DIVISION  
WICHITA, KS

INVOICED

DATE 11-21-95

INV. NO. 44101

11-11