

15135-20708'0000



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 20 1974  
12-20-74  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Mull Drilling Company, Inc.

Complete Address P. O. Box 1328, Great Bend, Kansas 67530

Lease Name Bremmer Well No. 1

Location C NE NE Sec. 5 Twp. 18 Rge. (E) (W) 21

County Ness Total Depth 4256'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698, Great Bend, Kansas License No. 670

Operation Completed: Hour 5 P Day 18 Month 12 Year 1974

The above well was plugged as follows:

Total Depth 4256' 8 5/8 csg set at 363' cwc 200 sx.

5 1/2 csg set at 4240' cw 100 sx. cem.

Filled 5 1/2 csg W/sd (4256-4225) dumped 4 sx cem W/dump bailer. (4225-4195)

Cutoff & recovered A/3600' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -70 sk cem -10 sk gel & water -released 8 5/8 plug & pumped 50 sk cem.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo P. Massey  
Well Plugging Supervisor

DATE 12/24/74  
INV. NO. 516-w