

15135-20738-0000
Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 29 1973
3-29-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Mack Oil Company

Complete Address 812 Union Center Wichita, Kansas

Lease Name Hanson Well No. 1

Location C NE NW Sec. 2 Twp. 18 Rge. (E) (W)²¹

County Ness Total Depth 4240'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling

Address Wichita, Kansas License No.

Operation Completed: Hour 3:15 P. Day 28 Month 3 Year 1973

The above well was plugged as follows:

Rtd 4240' 8 5/8 csg set at 264' cwc. Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 50 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/29/73
INV. NO. 7193-W

Signed: Leo F. Mansur
Well Plugging Supervisor