

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 6 - 6 - 72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name American Petrofina Co. of Texas

Complete Address Box 209 Russell, Ks

Lease Name Elsa B Well No. 1

Location SE/SW/SW Sec. 27 Twp. 32 Rge. 14 (E)      (W) W

County Barber Total Depth 4796

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Southwest Casing Pulling Co. Inc.

Address Box 364 Great Bend, Ks License No. 399

Operation Completed: Hour 3:00 PM Day 3 Month 3 Year 1972

The above well was plugged as follows:

985 ft 8 5/8 surface pipe cemented with 450 sacks. 4789 ft 5 1/2 long  
string cemented with 125 sacks. Top perf. 4748 ft. Sand back to  
4730 ft, 5 sacks cement with bailer. Pulled 2925 ft 5 1/2. Set 15 ft  
rock bridge at 375 ft. Fill hole with 6 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. Russell Bihart*  
Well Plugging Supervisor

INVOICED

DATE 3-6-72

INV. NO. 5284-112