

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
7-29-71
SEP 29 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Lonita Inc.
Complete Address 5900 E Central Suite 202 Wichita, Ks
Lease Name Hoagland Well No. 1
Location SE/SE/SW Sec. 22 Twp. 32 Rge. 14 (E) (W) W
County Barber Total Depth 4740
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Glenn & Smith Pipe Pulling Co.
Address 204 E 6th Ellinwood, Ks License No. 396
Operation Completed: Hour 2:00 PM Day 27 Month 9 Year 1971

The above well was plugged as follows:

284 ft 8 5/8 surface pipe cemented with 250 sacks. 4740 ft 4 1/2 long
string cemented with 125 sacks. Plug back at 4676 ft. Top perf.
4637 ft. Sand back to 4625 ft, 4 sacks cement with bailer. Pulled
3100 ft 4 1/2 Set 20 ft rock bridge at 260 ft. Fill hole with 4 yds
redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: E. Russell Bickert
Well Plugging Supervisor

INVOICED

DATE 9-29-71

INV. NO. 4382-00