

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1966
6-20-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Hull Well No. # 1

Location NE NE SE Sec. 34 Twp. 32 Rge. 14 (E) (W) W

County Barber Total Depth 4803'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 1:00PM Day 17th Month June Year 1966

The Above well was plugged as follows:

215' of 8 5/8" surface pipe, cement circulated. 4803' of 5 1/2" long string,
top of the cement at 4125'. Plug back T.D. 4798'. Top perforation 4764'.
10 sacks of cement was pumped on bottom. 610' of 5 1/2" long string was
recovered from the hole. Hole was filled with mud to 230', rock bridge
from 230' to 220', and cemented with 25 sacks. Hole was filled with mud
to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 6/20/66

INV. NO. 3408-W