

 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1963
9-16-63
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Gear Production Co., Inc.

Complete Address: 131 Laura, Wichita, Kansas

Lease Name Lake Well No. # 1

Location C SE NE Sec. 11 Twp. 32 Rge. 14 (E) (W) W

County Barber Total Depth 4075

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Comstock Pipe Pulling Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 4:00PM Day 9th Month September Year 1963

The Above well was plugged as follows:

1015' of 8 5/8" surface pipe, cement circulated. 4068' of 5 1/2" long string,
cemented with 100 sacks. Plugged back to 3920'. Top perferation 3891'.
Bottom sanded to 3880' and cemented with 5 sacks. Hole was filled with
mud to 300', 10' rock bridge, cemented with 20 sacks. Hole was filled
with mud to 40', 10' rock bridge, cemented with 10 sacks to base cellar.
3242' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9/16/63
INV. NO. 7739-W

Signed: Ardie Elving
Well Plugging Supervisor