

2 KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 19 1965  
10-19-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Aylward Drilling Company

Complete Address: 909 First National Bank Bldg., Wichita, Kansas

Lease Name Stumph-Smith "A" Well No. # 3

Location C SE NW Sec. 18 Twp. 32 Rge. 14 (E) (W) W

County Barber Total Depth 4775'

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Clarke Corporation, Inc.

Address: Chapin Bldg., Medicine Lodge, Kansas License No. 583

Operation Completed: Hour 2:45 PM Day 16th Month Oct. Year 1965

The Above well was plugged as follows:

215' of 8 5/8" surface pipe, cemented with 175 sacks. 4775' of 4 1/2" long  
string, cemented with 100 sacks. Top perferation 4740'. Bottom of the  
hole was sanded to 4725', and cemented with 3 sacks. 3400' of 4 1/2" long  
string was recovered from the hole. Hole was filled with mud to 215',  
rock bridge from 215 to 205', and cemented with 25 sacks. Hole was  
filled with mud to 40', rock bridge from 40' to 30', and cemented with  
10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

INVOICED

DATE 10/20/65

INV. NO. 2013-W