

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 10 1964

7-10-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name National Cooperative Refinery Assoc.

Complete Address: 305 Rule Bldg., Wichita, Kansas

Lease Name Stumph-Smith "B" Well No. # 1

Location C NW NW SW Sec. 18 Twp. 32 Rge. 14 (E) (W) (W)

County Barber Total Depth 5078

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour: 3:30PM Day 9th Month July Year 1964

The Above well was plugged as follows:

234' of 8 5/8" surface pipe, cemented with 200 sacks. 5077' of 5 1/2" long string, cemented with 125 sacks. Plug back to 5045. Top perforation 4710'.

Bottom of the hole was sanded to 4675', and cemented with 5 sacks. Hole was filled with mud to 240', bridged with 10' of rock, and cemented with 25 sacks. Hole was filled with mud to 40', bridged with 10' of rock, at 40', and cemented with 10 sacks to base of the cellar.

4000' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

DATE 7/10/64

INV. NO. 9444-0

Signed: Archie Elving
Well Plugging Supervisor