

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
Form CP-3
Rev. 6-4-68

FEB 26 1979
2-26-79
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 007-20607-0001 (of this well)

Operator's Full Name Birchall Petroleum, Inc.

Complete Address 5310 E-31st Street Suite 525, Tulsa Okla, 74135

Lease Name Stumph "A" Well No. 1-H

Location C-SE-SW- Sec. 18 Twp. 32 Rge. 14 (E) (W) X

County Barber Total Depth 4910

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Felso Casing Pulling -

Address Box 176, Chase, Kans - 67524 License No. 683

Operation Completed: Hour 1 pm Day 16 Month 2 Year 1979

The above well was plugged as follows:

222' - 8 5/8" Casing w/ 220 sack Cement - 4 1/2" Casing set @ 4850'
w/ 140 sack Cement - plug @ 4390' - Top prof. 4199' to 4210' Allied
Mixed & pumped 35 sack Common Cement in 4 1/2" casing - top @ 3870'
Pull 2990' - 4 1/2" Casing - Allied Mixed & pumped 5 sack bulls
20 sack gel-release plug - Mixed & pumped 100 sack 60/40 permix
Cement to top of casing, top cement contained 29 gal - 3 1/2 C.C
Shut in w/ 0' press. Cement fell to 485' - Allied mixed & pumped 75 sack
Cont w/ 16 1/2 gal - 49 sack 2 1/2 C.C & 1 sack bulls in 8 5/8" casing from 485' to zero -

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 2-27-79
INV. NO. 9161-W